


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Stafford County, Sec. 22 Twp. 22 Rge.      (E) 11 (W)  
Location as "NE/CNW/SWK" or footage from lines SW/c SE 1/4  
Lease Owner Lewis Drilling Company  
Lease Name Sleeper Well No. 1  
Office Address 607 Union National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 1-6-51 19    
Application for plugging filed 7-31-52 19    
Application for plugging approved 8-8-52 19    
Plugging commenced 7-31-52 19    
Plugging completed 8-5-52 19    
Reason for abandonment of well or producing formation Became non-producing



Locate well correctly on above  
Section Flat

If a producing well is abandoned, date of last production May 1952  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Merle Rives  
Producing formation                      Depth to top            Bottom            Total Depth of Well 3590 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	183'	None
				5-1/2"	3590'	2729'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from            feet to            feet for each plug set.

Sanded hole from 3590' to 3580' and ran 5 sacks of cement. Bailed hole from 30' to 195'. Mudded hole to 195', set 10' rock bridge and ran 20 sacks of cement. Mudded hole to 45', set 10' rock bridge and ran 10 sacks of cement. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Lester Matthew (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lester Matthew  
607 Union National Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of August, 1952  
Arthur R. Derrington  
Notary Public.

My commission expires August 20, 1952

24-2675-S 2-52-20M

**PLUGGING**  
FILE SEC 22T 22R 14  
BOOK PAGE 36 LINE 15

**RECEIVED**  
STATE CORPORATION COMMISSION  
AUG 21 1952  
8-21-52  
CONSERVATION DIVISION  
Wichita, Kansas

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Lewis Drilling Company, et al**

SEC. 22 T. 22 R. 11

FARM **Fair** Sleeper NO. 1

LOC. **SW/C 22 1/2**

TOTAL DEPTH **3590'**

COUNTY **Stafford**


COMM. **Jan. 6, 1951**

COMP. **Jan. 17, 1951**

KANSAS

SHOT OR TREATED

CONTRACTOR **Lewis Drilling Company**



ISSUED

CASING

20 10  
15 8-5/8" 153'  
12 6  
13 5

ELEVATION **1612' DF**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 0 - 195 Surface sand and clay
- 195 - 250 Red bed, sand and shale
- 250 - 520 Red bed shale
- 520 - 515 Anhydrite
- 515 - 1170 Shale and shells
- 1170 - 1125 Shale and brown lime
- 1125 - 2070 Brown lime
- 2070 - 2505 Shale and shells
- 2505 - 2615 Shale and lime
- 2615 - 2985 Shale and shells
- 2985 - 3110 Shale and lime
- 3110 - 3233 Shale and shells
- 3233 - 3250 Brown lime
- 3250 - 3275 Lime
- 3275 - 3315 Shale and lime
- 3315 - 3590 Lime
- 3590 - TD

GEOLOGICAL TOPS

Hestner	3089
Dodge	3111
Brown Lime	3230
Kansas City	3255
Conglomerate	3579

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) ss.

Hiram W. Lewis, Jr., Lewis Drilling Company, of lawful age, being first duly sworn under oath, states that the Lewis Drilling Company was the Contractor engaged for the drilling of the Fair No. 1, located in the Southeast Corner of the Southeast Quarter (SW/C 22 1/2) of Section 22, Township 22 South, Range 11 West, Stafford County, Kansas, and that the foregoing log is a true and correct copy of the log of the completed well.

LEWIS DRILLING COMPANY

By Hiram W. Lewis, Jr.  
Hiram W. Lewis, Jr.

Subscribed and sworn to before me, a Notary Public, in and for the county and state above mentioned, this 25th day of January, 1951.

Arthur R. Derrington  
Notary Public

My commission expires August 20, 1952.

**PLUGGING**  
FILE SEC-22-22-11-11  
BOOK PAGE 36-1-11-11

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 21 1952  
CONSERVATION DIVISION  
Wichita, Kansas