


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County. Sec. 22 Twp. 22S Rge. 11 ~~EW~~W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SW SW NW

Lease Owner Mustang Drilling & Exploration, Inc.
Lease Name Sleeper Well No. 1
Office Address P.O. Drawer 1609, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plot

Date Well completed October 24 19 81
Application for plugging filed October 24 19 81
Application for plugging approved October 24 19 81
Plugging commenced October 24 19 81
Plugging completed October 24 19 81
Reason for abandonment of well or producing formation

D & A
If a producing well is abandoned, date of last production 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Maurice V. Leslie, Nashville, KS
Producing formation Depth to top Bottom Total Depth of Well 3750
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 420 | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

620' 60 sx
400' 50 sx
40' 10 sx
Rathole 10 sx
50=50 poz 4% gel 3% cc

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1981

CONSERVATION DIVISION
Wichita, Kansas
10-30-81

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mustang Drilling & Exploration, Inc.

STATE OF Kansas COUNTY OF Barton, ss.
Kenneth Roach (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth O Roach
P.O. Drawer 1609, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of October, 1981

STATE NOTARY PUBLIC
BEVERLY SHEVSBART
April 14, 1982
My Appt. Exp.

Beverly Shevsbart
Notary Public.

My commission expires

DRILLERS' WELL LOG

OPERATOR: Mustang Drilling & Exploration, Inc.

WELL: No. 1 Sleeper

API # 15- 185- 21,380-0000

LOCATION: SW SW NW

Sec 22 -T 22S S-R 11W

COMMENCED: 10-16-81

COMPLETED: 10-24-81

ELEVATION: GL: 1796 DF: 1798 KB: 1801

TOTAL DEPTH: 3750

CASING: Surface: 8 5/8"; 23 #; set at 420 feet;
Cemented with 250 sacks Common cement; 3%cc; 2% gel

Production: ; #; set at feet;
Cemented with sacks cement;

| DEPTH: | FORMATION | FORMATION TOPS | |
|-------------|----------------|----------------|------------|
| 0 - 420 | Shale, Red Bed | Topeka | 2778 -977 |
| 420 - 531 | Anhydrite | Heebner | 3080 -1279 |
| 531 - 1915 | Shale | Toronto | 3101 -1300 |
| 1915 - 2778 | Lime, Shale | Douglas | 3117 -1316 |
| 2778 - 3080 | Lime | Brown Lime | 3224 -1423 |
| 3080 - 3084 | Shale | Lansing | 3248 -1447 |
| 3084 - 3117 | Lime, Shale | Base KC | 3504 -1703 |
| 3117 - 3224 | Shale | Viola | 3559 -1758 |
| 3224 - 3248 | Lime, Shale | Simpson Shale | 3579 -1778 |
| 3248 - 3504 | Lime | Simpson Sand | 3582 -1781 |
| 3504 - 3559 | Lime, Shale | Arbuckle | 3644 -1843 |
| 3559 - 3579 | Lime | RTD | 3750 |
| 3579 - 3582 | Shale | LTD | 3753 |
| 3582 - 3644 | Sand | | |
| 3644 - 3750 | Dolomite | | |
| 3750 | RTD | | |
| 3753 | LTD | | |

ACKNOWLEDGEMENT

STATE OF KANSAS, COUNTY OF BARTON, ss:

Before me, the undersigned, a Notary Public, within and for said county and state, on this 29th day of October, 1981, personally appeared Kenneth Roach to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary deed for the uses and purposes therein set forth.

Subscribed and sworn to before me this 29th day of October, 1981.

My Appointment Expires April 14, 1982
BEVERLY SHEWBART
 Notary Public, Kansas

Kenneth Roach
Beverly Shewbart
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 30 1981
 CONSERVATION DIVISION
 Wichita, Kansas