

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 22 Twp. 22S Rge. (E) 11 (W)

Location as "NE/CNW/SW" or footage from lines G - SE/4 SE/4 SW/4

Lease Owner Lion Oil Company

Lease Name Nolte Well No. 1

Office Address P. O. Box 639, Pratt, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 6-18 19 51

Application for plugging filed 1-12 19 53

Application for plugging approved 1-13 19 53

Plugging commenced 2-3 19 53

Plugging completed 2-5 19 53

Reason for abandonment of well or producing formation Well had ceased to produce

If a producing well is abandoned, date of last production 12-15 19 52

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives

Producing formation Depth to top Bottom Total Depth of Well 3588 Feet

Show depth and thickness of all water, oil and gas formations. Plugged Back TD 3285'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9-5/8"	239'	0'
				5-1/2"	3577'	2520'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole from 3285' to 3265' and ran 5 sacks of cement. Bailed fluid to 230', set 10' rock bridge and ran 20 sacks of cement. Mudded hole to 25', set 10' rock bridge and ran 10 sacks of cement on top to complete plugging.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company

Address Chase, Kansas

STATE OF KANSAS, COUNTY OF PRATT, ss.

Vernon Hayes (employee of owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Vernon Hayes

P. O. Box 639, Pratt, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of February 1953

Dan Houbek

Notary Public.

My commission expires August 29, 1955

24-2675-6 2-52-20M

PLUGGING
FILE SEC 22 T 22 R 11
BOOK PAGE 72 LINE 19

FEB 11 1953 2-11-53
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG NOLTE NO. 1

Lion Oil Company, Lease Owner

Section 22, Twp. 22 South, Rge. 11W

Garvey Oil, Contractor

Location: SE SE SW

Rotary Total Depth: 3587'

County: Stafford, Kansas

Commenced: May 31, 1951

Completed: June 11, 1951

Casing: 247' of 8 5/8"
3585' of 5 1/2"

All figures indicate bottom of formation:

125	Sand
185	Red Bed
247	Red Bed & Shale
529	Red Bed
552	Anhydrite
1570	Shale & Shells
2330	Lime & Shale
2675	Shale & Shells
3030	Lime & Shale
3502	Lime
3567	Lime & Shale
3587	Lime
3587'	R.T.D.

I hereby certify that this is a true and correct log of the above mentioned well.

GARVEY OIL

By

Eric H. Jager
Eric H. Jager

STATE OF KANSAS:

SS.

SEDGWICK COUNTY:

Subscribed to and sworn to before me, a Notary Public in said County and State this 18th day of June, 1951.

Charlotte Heidman
Notary Public

My commission expires: October 13, 1954

PLUGGING
FILE SEC 22 T 22 R 11W
BOOK PAGE 72 LINE 19

RECEIVED
THE CONSERVATION COMMISSION
JAN 13 1953
CONSERVATION DIVISION
Wichita, Kansas