

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERRY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15.185-21862-0000

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE NAME Gatton #1

WELL NUMBER _____

SPOT LOCATION SW SW SW

LEASE OPERATOR Bill Chew, Inc.

SEC. 22 TWP. 22S RGE. 11W (E) OR (W) _____

ADDRESS P.O. Box 90, Lyons, Ks. 67554

COUNTY Stafford

PHONE # () _____ OPERATORS LICENSE NO. _____

DATE WELL COMPLETED _____

CHARACTER OF WELL
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

PLUGGING COMMENCED 1/10/84

PLUGGING COMPLETED 1/19/84

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City

IS ACG-1 FILED? _____ IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM T.D. 3620'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	296'	none
				4 1/2"	3668'	2400'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Pumped bottom with 50 sacks cement, plug to 3220' Shot well at 2405'.
Pulled total of 57 joints of 4 1/2" casing. Plugged well with 3 hulls, 15 gel,
50 cement, 10 gel, 1 hull, plug, & 100 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050
ADDRESS Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, SS.

R. Darrell Kelso (EMPLOYEE OF OPERATOR) OR
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT
HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND
CORRECT, SO HELP ME GOD.

(SIGNATURE) R. Darrell Kelso

(ADDRESS) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO BEFORE ME THIS 20th DAY OF January, 1984



Irene Hoover
NOTARY PUBLIC

MY COMMISSION EXPIRES: _____

RECEIVED
STATE CORPORATION COMMISSION
1-23-84
JAN 23 1984

FORM CP-4
REVISED 06-83