

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,605-0000

LEASE NAME Sleeper "A"

WELL NUMBER 1

2970 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 22 TWP. 22S RGE. 11 ~~KRX&X(W)~~

COUNTY Stafford

Date Well Completed 9-23-89

Plugging Commenced 9-23-89

Plugging Completed 9-24-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Hellar Drilling Co., Inc.

ADDRESS 125 N. Market, Suite 1422, Wichita, KS 67202

PHONE#(316) 267-2845 OPERATORS LICENSE NO. 5015

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-24-89 (date)

by Dodge City District, Unattended (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3696'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	258'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. Circulate heavy mud in hole. 1st plug from 800' to 600' w/50 sx. 2nd plug from 5210' to 310' w/50 sx. 3rd plug from 290' to 130' w/40 sx. 4th plug from 40' SB to surface w/10 sx. Rathole- 15 sx. All cement 60/40 pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hellar Drilling Co., Inc. STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Sedgwick, ss. OCT 19 1989 10-1989

Jack K. Wharton (Employee of Operator or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 17th day of October, 19 89

Sharan J. Branstetter Notary Public
My Commission Expires: May 18, 1993

