

15-185-19346-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Fitting Building
Wichita, Kansas

WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH

Locate well correctly on above
Section Plat

Stafford County, Sec. 26 Twp. 23 Rge. 11 (E) (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines S/2 SE/4
Lease Owner Republic Natural Gas Company
Lease Name Krey Well No. B-1
Office Address Ellinwood, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 23. 19 45
Application for plugging filed. 19
Application for plugging approved January 23. 19 45
Plugging commenced January 23. 19 45
Plugging completed January 23. 19 45
Reason for abandonment of well or producing formation Viola formation and
Arbuckle formation non-productive.
If a producing well is abandoned, date of last production. 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Herb Kerr
Producing formation Depth to top Bottom Total Depth of Well 3870 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Misner	No Oil	3672'	3679'	10 3/4"	335'	None
Viola	No Oil	3684'	3697'			
Viola	No Oil	3713'	3718'			
Arbuckle	No Oil	3840'	3870'			
		No Oil String Run				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy rotary mud was placed in well from 3870' to 330'.
Drove bridge to 330' and placed 15 sacks cement from 330' to 302'. Filled hole with mud to 15' below surface and placed 10 sacks cement from 15' to bottom of cellar.

2-5-45

26 30 NW
2 45

FEB

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Republic Natural Gas Company
Address Box 918
Ellinwood, Kansas

STATE OF Kansas COUNTY OF Barton ss.

(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Helen M. Benscheidt
(Address) Ellinwood, Kansas

SUBSCRIBED AND SWORN to before me this 24th day of January, 1945

My commission expires My Commission Expires Aug. 30, 1947
Notary Public.



DRILLING LOG

15-185-19346-0000

REPUBLIC NATURAL GAS COMPANY

Lease Krey "B"Well No. 1Total Depth 3870'Comm. 1-6-45 Comp. Jan. 23, 1945Shot or Treated NoContractor Keyes Drilling CompanyRotary T. D. 3870'Cable Tools From To County StaffordSec. 26 Twp. 23 Rge. 11Location S/2 SE/4Elevation 1802'

CASING: 325' 10 3/4" 32.75# w/250 sx cement

Top Misner 3672' - 3679'

Top Viola 3684' - 3697'

Figures Indicate Bottom of Formations:

0'	-	100'	Clay & Sand
100'	-	337'	Clay & Sand
337'	-	500'	Red Bed
500'	-	520'	Anhydrite
520'	-	740'	Shale & Shells
740'	-	1240'	Shale & Shells
1240'	-	1475'	Shale & Shells
1475'	-	1485'	Shale & Shells
1485'	-	1575'	Lime & Shale
1575'	-	1685'	Shale & Lime
1685'	-	1800'	Lime, broken
1800'	-	1870'	Lime
1870'	-	1965'	Lime
1965'	-	2070'	Lime
2070'	-	2160'	Bro. Lime
2160'	-	2260'	Shale & Shells
2260'	-	2350'	Shale & Shells
2350'	-	2365'	Shale & Shells
2365'	-	2440'	Broken Lime
2440'	-	2525'	Shale & Shells
2525'	-	2615'	Shale & Shells
2615'	-	2680'	Lime
2680'	-	2755'	Lime
2755'	-	2850'	Lime, Broken
2850'	-	2925'	Lime
2925'	-	2965'	Lime
2965'	-	3015'	Lime
3015'	-	3035'	Lime
3035'	-	3105'	Lime
3105'	-	3170'	Lime
3170'	-	3225'	Lime
3225'	-	3275'	Lime

3275'	-	3315'	Lime
3315'	-	3370'	Lime
3370'	-	3420'	Lime
3420'	-	3450'	Lime, cherty
3450'	-	3510'	Lime
3510'	-	3560'	Lime
3560'	-	3600'	Lime
3600'	-	3640'	Shale & Lime
3640'	-	3665'	Shale & Lime
3665'	-	3700'	Lime, cherty
3700'	-	3716'	Lime
3716'	-	3735'	Lime
3735'	-	3760'	Lime & Shale
3760'	-	3770'	Shale
3770'	-	3795'	Shale & Lime
3795'	-	3815'	Lime & Shale
3815'	-	3870'	Shale & Lime
3870'	-		T.D.

3713'-18' D.S.T. 3 Jts. mud.
No show.

(SEE OVER FOR CORING RECORD)

26 30 11W
2 45

1

1

[illegible][illegible]