

15-185-01514-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County. Sec. 28 Twp. 23S Rge. 11 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW

Lease Owner Kantor Oil Company

Lease Name Riley Well No. 1

Office Address Box 846, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 19 40

Application for plugging filed August 18, 19 58

Application for plugging approved August 19, 19 58

Plugging commenced Sept. 1 19 58

Plugging completed Sept. 6 19 58

Reason for abandonment of well or producing formation

No longer economically profitable to operate.

If a producing well is abandoned, date of last production June 1958

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Fred Barfoot

Name of Conservation Agent who supervised plugging of this well

Producing formation L.K.C. Depth to top 3323 Bottom 3610 Total Depth of Well 3772 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
L.K.C.	Oil	3323	3610	8-5/8"	272'	
Viola	No Show	3648	3754	4-1/2"	3012	1600'
Brecciated Dolomite		3754	3762			
Arbuckle	Water	3762	3772			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with sand to 3440'. Dumped 5 sacks of cement. Shot pipe off at 1600'. Pulled pipe and mudded hole to 260'. Set 10' rock bridge and dumped 20 sacks of cement. Finished mudding to 25'. Set rock bridge and dumped 10 sacks of cement in top of surface.

*Rec'd 9-12-58*

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self

Address Hutchinson, Kansas

STATE OF Kans., COUNTY OF Reno, ss.

Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self

R. R. #4, Hutchinson, Kans. (Address)

SUBSCRIBED AND SWORN TO before me this 10th day of Sept. 19 58

*Dorothy Selig*  
Notary Public.

My commission expires August 12, 1961

PLUGGING  
FILE SEC 28 T 23 R 11W  
BOOK PAGE 124 LINE 1