

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22891-0000

LEASE NAME TRICHMANN

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

990 Ft. from (S) Section Line

330 Ft. from (E) Section Line

SEC. 18 TWP. 22 RGE. 12 (E) or (W)

COUNTY Stafford

Date Well Completed 2/1/93

Plugging Commenced 9/2/93

Plugging Completed 9/2-93

LEASE OPERATOR Grady Bolding Corporation

ADDRESS P. O. Box 486, Ellinwood, KS. 67526

PHONE# (316) 564-2240 OPERATORS LICENSE NO. 7383

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/27/93 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Conglomerate Depth to Top 3658' Bottom 3683' T.D. 3811'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Conglomerate	Sand	3658	3683	5 1/2	3807	1880

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sand dumped in hole from 3400' to T.D. 5 sacks of cement on top of sand; pulled casing (1880') Went down surface with 100# hulls followed by 10 sacks of Gel and 50 sacks 60-40 Poz. Cement 6% Gel. Put in another 100# hulls and 10 sacks Gel. Shut in. Released 8 5/8" dry hole plug and followed with 100 sacks 60-40 poz cement 6% gel. Shut in with 100# pressure. Maximum pressure was 500#. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company License STATE CORPORATION COMMISSION

Address Great Bend, KS. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Grady Bolding Corporation

STATE OF Kansas COUNTY OF Barton, ss.

Grady Bolding (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 486, Ellinwood, KS. 67526

SUBSCRIBED AND SWORN TO before me this 8th day of September, 19 93



Jenny Kasselmann
Notary Public

My Commission Expires: 7-16-94

RECEIVED
STATE CORPORATION COMMISSION
SEP 09 1993
9-9-93
CONSERVATION DIVISION
Wichita, Kansas