

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Stafford County, Sec. 18 Twp. 22S Rge. 12 (E) (W) X

Location as "NE/CNW/SW" or footage from lines C NW NE

Lease Owner Pan American Petroleum Corp.

Lease Name William Harms Well No. C-2

Office Address P. O. Box 548 Ellinwood, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 10-20-66 19

Plugging completed 10-28-66 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving

Producing formation Depth to top Bottom Total Depth of Well 3686 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	SECURITY	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
					8 5/8	250	None
					4 1/2	None	2413

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Rigged up unit. Sanded back from 3550' to 3340'. Mixed and dumped 3 sacks of cement on bridge at 3340'. Broke off tubing head. Cleaned out cellar. Rigged up jacks. Unpacked braden head.

Working pipe at 50,000# pressure. Shot pipe at 3187'. Working pipe. Shot pipe at 3121' - had 20" stretch.

Pumped 80 bbls. of water down 4 1/2" casing at 750# - broke back to 450#. Pumped 60 bbls. of oil at 425#. Pumped plug down with 48 bbls. of water. Let set till 10-25-66.

Working pipe - not loose. Run weight on Halliburton line - found plug at 2536'. Knocked plug to bottom. Shot pipe at 3019' - 2901' - 2814' - 2722' - 2603' - 2512' and 2407'.

Pulling pipe.

Finished pulling pipe. Pushed plug to 245' with 10' rock bridge. Mixed and dumped 10 sacks on bridge at 235'.

Bailed hole down for ready mix. Capped well.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes

P. O. Box 221 Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 2 day of November, 19 66

My commission expires May 27, 1969

Notary Public.