


WELL PLUGGING RECORD

FORMATION PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION Give All Information Completely Make Required Affidavit Mail or Defer Report to: Conservation Division State Corporation Commission 800 Bittling Building Wichita, Kansas

Strike out upper line when reporting plugging of formations.

Stafford County. Sec. 32 Twp. 22 Rge. 11 (W) Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SE SE SW Lease Owner Virginia Drilling Company, Inc. Lease Name Wells Well No. 1 Office Address 701 Brown Building, Wichita 2, Kansas Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole Date well completed December 8 1948 Application for plugging filed December 8 1948 Application for plugging approved December 8 1948 Plugging commenced December 8 1948 Plugging completed December 8 1948 Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. Stough Producing formation Depth to top Bottom Total Depth of Well 3715 Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: 8-5/8", 206, None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 200 feet to 30 feet for each plug set. Circulated heavy mud in hole. Pushed #1 plug to 200'. Cemented with 15 sacks cement. Circulated heavy mud to 30' of top. Pushed #2 plug to 30'. Cemented with 10 sacks.

12-15-48

RECEIVED Conservation Division STATE CORPORATION COMMISSION WICHITA, KANSAS

Correspondence regarding this well should be addressed to Virginia Drilling Company, Inc. Address 701 Brown Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. S. A. Murphy (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. A. Murphy 701 Brown Building, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 9th day of December, 1948. Notary Public.

My commission expires 2/5/49

PLUGGING FILE SEC. 32 T. 22 R. 11 W BOOK PAGE 72 LINE 40

Name: Wells No. 1  
 Location: SE/corner SW/4 Section 32-22S-11W, Stafford County, Kansas  
 Company: Virginia Drilling Company, Inc. et al  
 Contractor: Virginia Drilling Company, Inc.  
 Commenced: November 16, 1948  
 Completed: December 8, 1948  
 Total Depth: 3715  
 Elevation: 1805

FORMATION	DEPTH	Set 8-5/8" casing @ 206'
Sand-caly	0-40	CIRCULATE @ 3460 - 1 hr.
Shale	40-60	3576 - 1 hr.
Sand-redbed	60-206	3630
Shale	206-520	3679 - 1 hr.
Spot lime	520-538	
Shale-shells	538-1045	
Shale-shells	1045-1390	TOPS:
Shale-lime	1390-1465	Kansas City 3280
Lime-shale	1465-1490	Viola 3572
Lime (sandy)	1490-1530	Arbuckle 3675
Lime-shale	1530-2047	
Shale	2047-2140	
Lime-shale	2140-2605	Ft. Riley 1590
Broken Lime	2605-2680	Heebner 3111
Lime-shale	2680-2815	Top Brown Lime 3250
Lime (broken)	2815-2900	Conglomerate 3559
Lime	2900-2955	Simpson 3615
Lime-shale	2955-2998	
Sandy lime-shale	2998-3045	
Lime-shale	3045-3360	
Lime	3360-3399	
Lime-shale	3399-3434	
Shale-chert-sand	3517-3576	
Cherty Lime	3576-3595	
Lime-chert	3595-3614	
Shale-lime-chert-sand	3614-3650	
Shale	3650-3675	
Arbuckle	3675-3715	

Now comes S. A. Murphy, who states that he is familiar with the drilling of oil and gas wells and knows of his own knowledge that the Wells No. 1, located in the SE/corner of the SW/4 Section 32-22S-11W, Stafford County, Kansas, was drilled to a total depth of 3715 feet. Same was plugged and abandoned.

Subscribed and sworn to before me this 14<sup>th</sup> day of December, 1948.

My commission expires February 5, 1949.

RECEIVED  
 DEC 16 1948  
 STATE REGISTRATION  
 COMMISSION  
 KANSAS

PLUGGING  
 FILE NO. 32-22-11W  
 PAGE 72 LINE 40