

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-21,081

LEASE NAME Heyen

WELL NUMBER #1

SPOT LOCATION NE NW NW

SEC. 32 TWP. 22 RGE. 11 (E or (W))

COUNTY Stafford

Date Well Completed \_\_\_\_\_

Plugging Commenced 4-16-86

Plugging Completed 4-21-86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Iannitti Oil Company

ADDRESS Box 308, Great Bend, Kansas.

PHONE # (316-792-1934) OPERATORS LICENSE NO. 6588

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One (1)

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3570'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	291'	None
				5-1/2"	3568'	2,806.54'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped sand to 3475' and 5 sacks cement. Shot casing at 2800'. Pulled 90 jts. of 5-1/2" casing. B.J. Titan squeezed well with 2 sacks hulls, 15 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 150 sacks 60/40 pozmix cement with 6% added gel. Maximum pressure was 700 psi and shutin 350 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold  
James W. Rockhold  
(Address) Box 698, Gt. Bend, Ks. 67530

4-23-86

APR 23 1986

CONSERVATION DIVISION  
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 22nd day of April, 1986

STATE NOTARY PUBLIC  
KANSAS  
IONA M. LEATHERMAN  
Barton County, Kansas  
My Appt. Exp. 4-26-87

Iona M. Leatherman  
Notary Public

My Commission expires:

# WOODMAN & IANNITTI DRILLING COMPANY

*Rotary Drilling Contractors*

1008 DOUGLAS BUILDING  
104 S. BROADWAY  
WICHITA, KANSAS 67202

July 30, 1980

Company;	Iannitti Oil Co.
Farm;	#1 Heyen
Location;	NE NW NW
Section;	32-22S-11W
County;	Stafford
Contractor;	Woodman & Iannitti Drilling Co.
Comm;	July 21, 1980
Compl;	July 28, 1980
Total Depth;	3570'
Casing;	8 5/8 @ 291 w/225 sx. 5 1/2 @ 3568 w/100 sx.

### Figures Indicate Bottom Of Formations

100	Sand & top soil
291	Redbed
547	Redbed
566	Anhy
1350	Shale
1675	Shale
2125	Shale & lime
2400	Shale
2810	Shale & lime
3300	Lime & shale
3460	Lime
3538	Lime & shale
3570	Lime & shale

I certify the above to be a true and correct copy of the drillers log to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.

*D. J. Iannitti*  
D. J. Iannitti

RECEIVED  
STATE CORPORATION COMMISSION

APR 15 1986

CONSERVATION DIVISION  
Wichita, Kansas