

15-185-21780-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Stafford SEC. 28 TWP. 22 RGE. 11 E/W  
 Location as in quarters or footage from lines:  
SE NE SW

		28	

Lease Owner Grady Bolding Corporation License # 7383  
 Lease Name Lofland Well No. # 1  
 Office Address Box 244, Great Bend, Kansas 67530  
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
 Date Well Completed 6-4-83  
 Application for plugging filed Yes  
 Plugging commenced 12-22-83  
 Plugging completed 1-12-84  
 Reason for abandonment of well or producing formation Depleted

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz

Producing formation KANSAS City Depth to top 3447' bottom 3452' T.D. 3690'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	288'	None
				5-1/2"	3689'	2,963.05'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Dumped sand to 3065' and 5 sacks cement. Shot casing at 3000' and 2900'  
Pulled 70 joints of 5-1/2" casing. Sun squeezed well with 3 sacks hulls,  
10 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released  
plug and pumped 125 sacks 50/50 Poemix cement with 2% added gel and  
3% Calcium chloridie.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
 James W. Rockhold, Box 698, Great Bend, Kansas 67530  
 (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of January, 1984

My Commission expires: 

Jona M. Leatherman  
 Notary Public.

STATE CORPORATION  
 JAN 17 1984  
 CONSERVATION  
 Wichita, Kansas

1-17-84