

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Stafford County. Sec. 28 Twp. 22 Rge. 11 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NW SW

Lease Owner Petroleum, Inc.

Lease Name Bagley Well No. 1

Office Address 305 East Third, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 9, 19 53

Application for plugging filed October 9, 19 53

Application for plugging approved October 9, 19 53

Plugging commenced October 9, 19 53

Plugging completed October 9, 19 53

Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 3690 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	210'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 208' and set wooden plug  
at 208'. Placed 1/4 sack hulls ahead  
of plug set at 208'. Cemented and  
displaced 15 sacks cement through drill  
pipe onto plug and hulls at 208'. Mud-  
ded up to 35' and set second wooden plug  
at 35'. Placed 1/4 sack hulls on top of  
plug at 35'. Filled hole to bottom of  
well cellar with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company

Address R.R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
W.W. Fisher (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W.W. Fisher


305 East Third, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of October, 19 53

My commission expires October 13, 1954

Charlotte Sherman Notary Public.

24-7368-5 3-53-20M



OCT 24 1953 10-24-53  
DIVISION

DRILLER'S LOG BAGLEY #1

Petroleum, Inc., Operator

Section 28, Twp. 22S, Rge. 11W

Garvey Drilling Company, Contractor

Location: NE NW SW

Drilling Commenced: September 30, 1953

County: Stafford County, Kansas

Drilling Completed: October 9, 1953

Production: D & A

Casing Record: 8 5/8" @ 210' w/200 sax

Figures below indicate bottom of formation:

100 Surface and Sand  
 120 Red Bed & Hard Sand  
 210 Red Bed & Shale  
 545 Red Bed  
 565 Anhydrite  
 1365 Shale & Shells  
 3218 Lime & Shale  
 3466 Lime  
 3548 Lime & Shale  
 3555 Conglomerate  
 3571 Chert  
 3592 Chert  
 3620 Shale  
 3655 Shale & Lime  
 3690 Lime  
  
 3690 R.T.D.

Tops:

Heebnor: 3088(-1275)  
 Toronto: 3108(-1295)  
 Douglas: 3123(-1310)  
 Brown Lime: 3228(-1415)  
 Lansing: 3253(-1440)  
 Conglomerate: 3548(-1735)  
 Viola: 3555(-1742)  
 Simpson: 3592(-1779)  
 Arbuckle: 3650(-1837)

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By *W. W. Fish*

STATE OF KANSAS )  
 ) SS:  
 COUNTY OF SEDGWICK )

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 23rd day of October, 1953.

**PLUGGING**  
 FILE SEC 28 T 22 R 11W  
 BOOK PAGE 135 LINE 9

*John L. Shuler*  
Notary Public

My commission expires: October 13, 1954