

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 28 Twp. 22S Rge. (E) 11 (W)

Location as "NE/CNW/SW" or footage from lines SE SW SW
Lease Owner Lee Phillips Oil Company
Lease Name Lofland Well No. 1
Office Address 1532 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 9, 1965
Application for plugging filed November 9, 1965
Application for plugging approved November 9, 1965
Plugging commenced November 9, 1965
Plugging completed November 9, 1965
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3630 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 240 feet. Followed by wooden plug and 1/4 sack hulls. Placed 25 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/4 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

11-22-65

NOV 22 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.
Address 412 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves

412 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of November, 1965

Betty Brandt
Notary Public.

My commission expires April 30, 1967

ROTARY DRILLERS' LOG

OPERATOR: Lee Phillips Oil Company DRILLING COMMENCED: November 2, 1965
 1532 Wichita Plaza
 Wichita, Kansas

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: November 9, 1965
 412 Union Center
 Wichita, Kansas

CASING RECORD: 13 Jts. 250' 8-5/8" LOCATION: Lofland No. 1
 cemented with 325 sacks SE SW SW
 Section 28-22S-11W
 Stafford County, Kansas

0 - 80	Sod & clay
80 - 135	Sand
135 - 185	Red bed & shale
185 - 270	Shale & red bed
270 - 400	Red bed
400 - 550	Shale & shells
550 - 1395	Shale, shells & red bed
1395 - 1510	Shale with lime
1510 - 1914	Lime
1914 - 2105	Lime with shale streaks
2105 - 2405	Lime & shale
2405 - 2800	Shale & lime
2800 - 3075	Lime
3075 - 3080	Shale
3080 - 3210	Lime & shale
3210 - 3213	Shale
3213 - 3242	Brown lime & shale
3242 - 3475	Lime
3475 - 3536	Lime & shale
3536 - 3570	Cherty lime
3570 - 3620	Sandy shale
3620 - 3630	Sandy shale & lime
3630	Rotary Total Depth

RECEIVED
 STATE INCORPORATION COMMISSION
 NOV 22 1965
 INSERVATION DIVISION
 Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By James Graves
President

STATE OF KANSAS)
) SS:
BUTLER CO UNTY)

Subscribed and sworn to before me, a Notary Public, this 18th of November, 1965.

My commission expires:
April 30, 1967

Betty Brandt
Betty Brandt Notary Public