

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Stafford

County, Sec. 19 Twp. 22S Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines SE SE NW

Lease Owner Peel-Hardman Producers

Lease Name Brensing

Well No. 1

Office Address P.O. Box 359, Hoisington, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 22 1949

Application for plugging filed April 22 1949

Application for plugging approved April 22 1949

Plugging commenced April 22 1949

Plugging completed April 22 1949

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3775 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	276'	8 5/8"	276'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3775' - 272' - Heavy Rotary Mud  
272' - 270' - Wooden Plug  
270' - 232 1/2' - 15 sacks cement  
232 1/2' - 32' - Heavy Rotary Mud  
32' - 30' - Wooden Plug  
30' - 6' - 10 sacks cement  
6' - Surface - Cellar

RECEIVED

Conservation-Div.

APR 27 1949

4-27-49

STATE CORPORATION  
COMMISSION  
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Peel-Hardman Producers

Address P.O. Box 359  
Hoisington, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Glenn Peel Drilling Co., Inc.

(employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. GLENN PEEL DRILLING COMPANY, INC.

(Signature)

BY *Glenn Peel*

P.O. Box 359, Hoisington, Kansas  
(Address)


SUBSCRIBED AND SWORN to before me this 26th day of April, 1949.

June 4, 1951

*Marion M. Herber*

Notary Public.

My commission expires



DRILLER'S LOG

Company: Peel-Hardman Producers  
R. W. Shields  
Farm: Brensing Well No. 1

Sec. 19 Twp. 22S Rge. 12W  
SE SE NW

Total Depth: 3775'

County: Stafford,  
Kansas

Comm.: 4-12-49 Comp.: 4-22-49  
Contractor: Glenn Peel Drilling Co., Inc.  
Casing:  
8 5/8" 276' cem.

Elevation:  
Production: Dry

Figures below indicate bottom of formations

Sand and Surface Clay	0 -	40
Shale		60
Sand and Gravel		210
Red Bed		276
Shale and Sand		500
Red Bed		1225
Salt and Shale		1405
Shale and Shells		1650
Lime and Shale		1830
Lime		2000
Lime and Chert		2050
Shale		2265
Shale and Shells		2650
Shale and Lime		2790
Lime and Shale		2900
Shale and Lime		3015
Lime and Shale		3200
Broken Lime		3310
Lime		3695
Cherty Lime		3725
Lime and Shale		3775
Total Depth		3775

**RECEIVED**

Conservation-Div.

APR 27 1949

STATE CORPORATION  
COMMISSION  
KANSAS

This is to certify that the above information is, to the best of our knowledge, true and correct.

GLENN PEEL DRILLING COMPANY, INC.

BY: Mendell E. Peel

SUBSCRIBED AND SWORN to before me this 26th day of April, 1949

My commission expires June 4, 1951

Marion M. Herd  
Notary Public

