

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

**RECEIVED**  
STATE CORPORATION COMMISSION

DEC 3 1964

CONSERVATION DIVISION  
Wichita, Kansas

12-3-64

Operator's Full Name Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza, Wichita, Kansas

Lease Name Drach Well No. # 1

Location C NW SW NE Sec. 18 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3747

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Rains & Williamson Oil Company

Address: 1425 Wichita Plaza, Wichita, Kansas License No.     

Operation Completed: Hour 2:15AM Day 2nd Month Dec. Year 1964

The Above well was plugged as follows:

282' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fluid  
level in the hole was at 230', 1st cementing plug and 1/4 sack of hulls  
was pushed in fluid to 275', and cemented with 25 sacks, through the  
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing  
plug, bridged solid with dry cement and hulls on fluid at 40', and  
cemented with 10 sacks to the base of the cellar. Rat hole bridged and  
cemented with 2 sacks.

I hereby certify that ~~the~~ **INVOLVED** above well was plugged as herein stated.

DATE 12/3/64  
INV. NO. 279-11

Signed: Archie Elving  
Well Plugging Supervisor