


Form CP-3
Rev. 6-26-62


 KANSAS
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 31 1966
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assitant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Operator's Full Name Pan American Petroleum Corporation
 Complete Address: P. O. Box 432, Liberal, Kansas
 Lease Name W. Harms "C" Well No. # 2
 Location C N/2 NW NE Sec. 18 Twp. 22 Rge. 12 (E) (W) W
 County Stafford Total Depth 3691'
 Abandoned Oil Well X Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated:
 Plugging Contractor: Forbes Casing Pulling, Inc.
 Address: Box 221, Great Bend, Kansas License No. 49
 Operation Completed: Hour 11:45AM Day 28th Month Oct. Year 1966

The Above well was plugged as follows:

246' of 8 5/8" surface pipe, cemented with 150 sacks. 3686' of 4 1/2" long
string, cemented with 100 sacks. Plug back T.D. 3550'. Top perferation 3487'.
Bottom of the hole was sanded to 3340', and cemented with 3 sacks. through
the dump bailer. 2407' of 4 1/2" long string was recovered from the hole.
Bridge plug was pushed in fluid to 245', rock bridge from 245' to 235'. 10
sacks of cement was mixed in a barrel, and put on plug at 235', through the
dump bailer, and let set over-night. Next day hole was bailed dry, and hole
was filled with 3 yards of ready-mix cement from 205' to the base of the cell-
ar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 10/31/66

INV. NO. 4205-u