

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 112-30

LOCATION SW-SW-NW

SEC. 32 TWP. 22 RGE. 11

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease Bagley

Operator J. W. Patterson & Son Address Box # 67 - Sterling - Kansas

Field \_\_\_\_\_ County Stafford

Total Depth 3600 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 10 3/4 - 23 1/2. Circulated with cement.  
7" casing set at 3575. Filled back from bottom  
to 3455 with chert - Dumped 5 sacks of cement  
at 3555 - Shot off & pulled the 7" casing - Filled  
with mud to 23 1/2. Set Brock Bridge & 20 sacks  
of cement at 23 1/2. Mud to 30 ft. Plug & 10 sacks  
of cement at the surface*

*J. W. Patterson & Son  
Plugging Contractors*

*9-22-49*

RECEIVED C. D. Stough -  
District Conservation Agent

Conservation Div.

Date 9-20-49

**PLUGGING**  
FILE SEC 32 TWP 22 RGE 11  
BOOK PAGE 118 LINE 30

SEP 22 1949  
CORPORATION  
COMMISSION  
KANSAS