

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 4 - 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Duke Drlg. Co. Inc.

Complete Address 1105 Williams Great Bend, Ks

Lease Name Krankenbergl Well No. 1

Location SE/SW/SE Sec. 19 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3775

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Forbes Casing Pulling Co. Inc.

Address Box 221 Great Bend, Ks License No. 49

Operation Completed: Hour 4:00 PM Day 2 Month 12 Year 1970

The above well was plugged as follows:

263 ft of 8 5/8 surface pipe cemented with 250 sacks. 3774 ft of  
5 1/2 long string cemented with 50 sacks & 450 gals. of latex. Top perf.  
3718 ft. Sand back to 3700 ft, 5 sacks cement with bailer. Pulled  
2100 ft of 5 1/2. Set 10 ft rock bridge at 240 ft. Fill hole with  
4 yds of redimix to base of cellar.

I hereby certify that the above well was plugged as herein stated,

INVOICED

Signed: D. Russell B. Hunter  
Well Plugging Supervisor

DATE 12/4/70  
INV. NO. 2983-4