

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

**RECEIVED**  
STATE CORPORATION COMMISSION

JUL 16 1964

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Woody's Quality Oil Company

Complete Address: 1119 Cravens Bldg., Oklahoma City, Oklahoma

Lease Name Krankenber Well No. # 1

Location SE SW SE Sec. 19 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3775

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Duke Drilling Company

Address: Box 823, Great Bend, Kansas License No.     

Operation Completed: Hour 5:30AM Day 14th Month July Year 1964

The Above well was plugged as follows:

264' of 8 5/8" surface pipe, cemented with 225 sacks. Fluid level was  
up in the hole. 1st cementing plug and 1/2 sack hulls, was pushed in  
fluid to 250', and cemented with 25 sacks, through the drill pipe. Hole  
was filled with drilling mud to 40', 2nd cementing plug, bridged solid  
with hulls, on fluid at 40', and cemented with 10 sacks to base of the  
cellar. Rat hole bridged and cemented with 2 sacks.

**INVOICED**

I hereby certify that the above well was plugged as herein stated.

DATE 7/16/64

INV. NO. 9485-12

Signed: Archie Elving  
Well Plugging Supervisor