

Y
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

NOV 3 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Lee Phillips Oil Co., & Graves Drilling Co., Inc.

Complete Address: 1532 Wichita Plaza, Wichita, Kansas

Lease Name Brensing Well No. # 1

Location NE SW NW Sec. 19 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3760'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Graves Drilling Company, Inc.

Address: 412 Union Center, Wichita, Kansas License No.

Operation Completed: Hour 9:00 PM Day 1st Month Nov. Year 1965

The Above well was plugged as follows:

264' of 8 5/8" surface pipe, cement circulated with 300 sacks. Fluid
in the hole was at 248', 1st cementing plug bridged solid with dry
cement and hulls on fluid at 248', and cemented with 25 sacks. Hole was
filled with drilling mud to 40', 2nd cementing plug, bridged solid with
dry cement and hulls on fluid at 40', and cemented with 10 sacks to the
base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/3/65
INV. NO. 2106-W