

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

OCT 11 1965

CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Donald T. Ingling

Complete Address: 615 First National Bank Bldg., Wichita, Kansas

Lease Name Curtis Well No. # 1

Location C S/2 SE SW Sec. 19 Twp. 22 Rge. 12 (E) (W)

County Stafford Total Depth 3782'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Donald T. Ingling Drilling Company

Address: 615 First National Bank Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 12:30PM Day 8th Month Oct. Year 1965

The Above well was plugged as follows:

260' of 8 5/8" surface pipe, cemented with 200 sacks. Fluid level in
the hole was at 120'. 1st cementing plug and 1 sack of hulls was pushed
in fluid to 240', and cemented with 25 sacks, through the drill pipe.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with hulls on fluid at 40', and cemented with 10 sacks to the
base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICE

Signed: Archie Elving
Well Plugging Supervisor

DATE 10/11/65
REV. 1961-4