

B

DISTRICT CONSERVATION AGENT'S REPORT



12-30-43

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW NW

SEC. 17 TWP. 22 RGE. 12W

Dry Hole _____ Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 7 Lease Smith

Operator Alpine Oil & Royalty Co. Address Beacon Bldg. Wichita, Kansas

Field _____ County Stafford

Total Depth 3728 Feet.

(Describe briefly the manner in which the well was plugged)

Hole filled with mud from 3728 to
240 and bridge at 240 and cement
to 210 and mud and bridge to
20 ft and cement to 4 ft

PLUGGING
FILE 17 22 1 24
BOOK 10 LINE 39

A. T. Alexander
District Conservation Agent

Date 12-28-43

Handwritten notes:
20
21
22

A. SMITH #2

The Northwest Quarter (NW/4) of Sec.
Seventeen (17), Township Twenty-Two
(22) South, Range Twelve (12) West
Stafford County, Kansas

Started rigging up 12-3-43
Tearing out tools 12-26-43

Set 6 joints of 10 3/4", 240' Spiral Weld Casing at 240'
with 150 sacks of cement

FORMATION	FROM	TO
Surface Clay & sand	0	40
Sand	40	190
Gravel & Sand	90	135
Sand & Shells	135	165
Shale & Shells	165	255
Shale & Red Bed	255	680
Lime	680	695
Shale & Red Bed	695	820
Shale & Shells	820	1185
Salt & Shells	1185	1295
Salt	1295	1470
Salt & Shells	1470	1560
Broken Lime	1560	1600
Shale & Shells	1600	1635
Lime	1635	2085
Broken Lime	2085	2140
Shale & Shells	2140	2160
Lime	2160	2335
Lime & Shale	2335	2360
Lime	2360	2430
Lime & Shale	2430	2495
Shale	2495	2630
Shale & Lime Shells	2730	2790
Lime	2790	2835
Lime & Shale	2835	2880
Lime, Shale & Boulders	2880	2970
Lime	2970	2985
Sandy Lime	2985	3010
Lime	3010	3100
Shale & Boulders	3100	3125
Lime	3125	3330
Lime & Shale	3330	3345
Lime	3345	3420
Broken Lime & Shale	3420	3440
Lime	3440	3545
Lime & Shale	3545	3665
Lime	3565	3623
Chirty Lime	3623	3645
Shale	3645	3693
Lime	3693	3728
	3728	

TOTAL DEPTH

I, W. A. Grant, partner of Harbar
Drilling Company, certify that to the
best of my knowledge, the above log is
true and correct.



Subscribed and sworn to before me this
29th day of December, 1943.

Margaret O. Kelly
Notary Public

My commission expires April 7, 1947.

PLUGGING

THIS LOG 171-222-122
WAS MADE 3-12-43

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Stafford

County. Sec. 17 Twp. 22 Rge. 12 (E) W. (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW $\frac{1}{4}$ NW $\frac{1}{4}$

Lease Owner Alpine Oil Company,

Lease Name A. Smith Well No. 2

Office Address Bitting Building, Wichita, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 26th 19 43

Application for plugging filed December 26th 19 43

Application for plugging approved December 26th 19 43

Plugging commenced December 26th 19 43

Plugging completed December 26th 19 43

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well C. T. Alexander

Producing formation Depth to top Bottom Total Depth of Well 3728 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sand	Water	60'	75'	10 3/4"	246'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged with heavy mud from 3728' to 246' with permanent plug placed @ 246' and cemented with 20 sacks from 246' to 206'
Heavy mud from 206' to 26' and cemented with 10 sacks of cement from 26' to 6'.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Harb Drilling Company

Address 1019 Central Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Jim Adkins

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

1019 Central Building, 1502- 12th St., Great Bend, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of December, 19 43.

My commission expires April 2, 19 47

