

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford County, Sec. 28 Twp. 22 Rge. 14 W. (E) (W)

Location as "NE/CNW/SW" or footage from lines NW SE SE

Lease Owner Franco Central Oil Company

Lease Name Symms Well No. 1

Office Address Fourth National Bank Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-11 19 54

Application for plugging filed 3-11 19 54

Application for plugging approved 3-11 19 54

Plugging commenced 3-11 19 54

Plugging completed 3-11 19 54

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3958 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	LOG ATTACHED					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 240' with heavy mud, set plug and cemented with 20 sacks through drill pipe. Filled hole with heavy mud to 40', set plug and cemented with 10 sacks

RECEIVED
STATE CORPORATION COMMISSION

MAR 15 1954

3-18-54

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor The Carl Todd Drilling Company

Address 404 KFH Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

L. M. Clothier (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. M. Clothier

Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of March, 1954

Rebecca Hill

Notary Public.

My commission expires October 21, 1954

24-2675-S 2-52-20M

PLUGGING
FILE SEC 28 T 22 R 14 W
BOOK PAGE 18 LINE 37

THE CARL TODD DRILLING COMPANY
401 KFH Building
Wichita, Kansas

FRANCO CENTRAL OIL COMPANY
#1 Symms
NW SE SE Sec. 28-22-14W
Stafford County, Kansas

COMMENCED: March 1, 1954
COMPLETED: March 11, 1954

ELEVATION: 1947 DF

CASING RECORD

- 0 - 210 Surface clay and sand
- 210 - 255 Red shale and shells
- 255 - 330 Shale and shells
- 330 - 390 Sand
- 390 - 455 Red Bed
- 455 - 850 Red Bed and shale
- 850 - 875 Anhydrite
- 875 - 1200 Shale, shells and salt
- 1200 - 1715 Shale and shells
- 1715 - 1865 Shale and shells
- 1865 - 2030 Lime and shale
- 2030 - 2180 Lime and shale
- 2180 - 2290 Lime and shale
- 2290 - 2490 Shale and lime
- 2490 - 2680 Shale
- 2680 - 2845 Lime and shale
- 2845 - 2975 Shale and lime
- 2975 - 3110 Shale
- 3110 - 3195 Lime and shale
- 3195 - 3250 Shale
- 3250 - 3300 Lime
- 3300 - 3375 Lime
- 3375 - 3395 Lime
- 3395 - 3485 Lime and shale
- 3485 - 3506 Shale
- 3506 - 3565 Lime
- 3565 - 3635 Lime
- 3635 - 3685 Lime
- 3685 - 3700 Lime
- 3700 - 3735 Lime
- 3735 - 3805 Lime and shale
- 3805 - 3825 Cong.
- 3825 - 3869 Lime
- 3869 - 3907 Lime and shale
- 3907 - 3940 Lime and shale
- 3940 - 3950 Lime
- 3950 - 3958 Lime
- 3958 Rotary Total Depth

Set 8-5/8" surface casing at
255' with 185 sacks cement

TOPS

Heebner	3366
Brown Lime	3494
Lansing	3505
Cong.	3809
Viola	3822
Simpson	3877
Arbuckle	3941

I hereby certify that the above is a true and correct log, to
the best of my knowledge and belief.

THE CARL TODD DRILLING COMPANY
Carl Todd

RECEIVED
STATE CORPORATION COMMISSION
MAR 18 1954
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 28 T 22 R 14W
BOOK PAGE 18 LINE 37