


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 28 Twp. 22 Rge. 14 (#7) (W) X

Location as "NE/CNW/SW" or footage from lines SW SW NW
Lease Owner Petroleum, Inc.
Lease Name Tucker "F" Well No. 1
Office Address Route 2, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 7, 1963
Application for plugging filed December 7, 1963
Application for plugging approved December 7, 1963
Plugging commenced December 7, 1963
Plugging completed December 7, 1963
Reason for abandonment of well or producing formation No Produccable Zones.



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production --- 19---
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4034' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	254'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded up with heavy mud to 250' followed by wooden plug, 1/4 sack hulls & 25 sacks cement. Mudded up with heavy mud to 40', followed by wodden plug & 1/4 sack hulls. Placed 10 sacks of cement on top of hulls to base of well cellar.

RECEIVED
STATE CORPORATION COMMISSION

DEC 27 1963

CONSERVATION DIVISION
Wichita, Kansas

12-27-63

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Garvey Drilling Company
Address Route 2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Monte Chadd (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Monte Chadd, Dist. Prod. Supt.

(Signature) Monte Chadd
Route 2, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of December, 19 63

My commission expires September 23, 1967.

Edward B. Jensen
Notary Public.

WELL LOG

COMPANY **Petroleum, Inc.**

SEC. **28 T. 22S R. 14W**

FARM **Tucker**

NO. **F-1**

LOC. **SW SW NW**


TOTAL DEPTH **4034'**

COUNTY **Stafford**

COMM. **11-27-63**

COMP. **12-7-63**

CONTRACTOR **Garvey Drilling Company**



CASING **8 5/8" @ 254' w/225 sx**

ELEVATION **1957' DF**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

- 256' Surface Soil and Shale
- 810' Anhydrite
- 880' Shale and Shells
- 915' Anhydrite
- 1700' Shale and Shells
- 1960' Lime and Shale
- 2230' Lime
- 2555' Lime and Shale
- 2760' Shale w/Lime Streaks
- 3095' Shale and Lime
- 3215' Lime
- 3330' Lime and Shale
- 3515' Shale and Lime
- 3830' Lime
- 3940' Lime and Chert
- 3990' Simpson
- 4000' Sandy Shale and Lime
- 4034' Lime and Shale
- 4034' RTD

RECEIVED
STATE CORPORATION COMMISSION

DEC 27 1963

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } SS

I, Sam N. Stephens of Garvey Drilling Company
upon oath state the above and foregoing is a true and correct copy of the log of the Tucker F-1 well.

Subscribed and sworn to before me this 16th day of December 19 63

My Commission Expires: September 23rd, 1967

NOTARY PUBLIC