


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Stafford County, Sec. 25 Twp. 22S Rge. XXX 11 (W)
Location as "NE/CNW/SW" or footage from lines NW-NW-SW
Lease Owner Sunray Oil Corporation
Lease Name Ross Well No. 1
Office Address P. O. Box 195, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 2 19 54
Application for plugging filed April 5 19 54
Application for plugging approved April 6 19 54
Plugging commenced April 6 19 54
Plugging completed April 13 19 54
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Merle Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3870 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Haebner		3312		8 5/8	320'	none
Brown Lime		3354		5 1/2	3698'	3381'
Lansing-KC	water/oil	3458	3693			
Marmaton		3702				
Conglomerate		3720				
Viola		3748				
Simpson		3810				
Arbuckle	water	3856	3870			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Original total depth was 3870'. Cement filled to 3667' inside of pipe and was not drilled out. Filled hole with sand from 3667' to 3600' and ran 5 sacks of cement. Circulated pipe with mud. Set a 10' rock bridge at 300' and ran 20 sacks of cement at 290'. Mudded hole to top and ran 10 sacks of cement. Plugged completed.

Well log attached.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Robert K. Crouch (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert K. Crouch
Box 195, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of April, 19 54

My commission expires December 24, 1956

Notary Public.
STATE CORPORATION COMMISSION

PLUGGING APR 24 1954 4-24-54
 FILE SEC 25 T 22 R 14 W
 BOOK PAGE 245 LINE 6
 STATE CORPORATION COMMISSION
 WICHITA, KANSAS

Sunray Oil Corporation
Tulsa, Oklahoma

Tulsa, Oklahoma
March 29, 1954

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: March 16, 1954
Drilling Completed: March 27, 1954

Ross #1 W/2 SW/4 Section
25-22S-14W, Stafford
County, Kansas.

DRILLERS LOG

Sand, Shale & Shells	0-329
Red Bed	329-820
Anhydrite	820-850
Shale & Shells	850-1650
Shale & Lime	1650-1730
Lime & Shale	1730-2460
Shale & Lime	2460-2790
Lime & Shale	2790-3365
Shale & Broken Lime	3365-3445
Lime	3445-3770
Chert & Lime	3770-3805
Lime	3805-3834
Simpson	3834-3856
Arbuckle	3856-3870 TD

I, Frank E. Stickle hereby certify the above to be a true and complete Drillers Log of Sunray Oil Corporation's Ross #1 W/2 SW/4 Section 25-22S-14W, Stafford County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1956
My Commission Expires

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1954
CONSERVATION DIVISION
KANSAS

PLUGGING
FILE NO. 25-22S-14W
BOOK PAGE 25 LINE 6