


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County, Sec. 21 Twp. 22 Rge. (E) 14 (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW NW SW
Lease Owner Westgate-Greenland Oil Company
Lease Name Sutton Well No. 1
Office Address 1009 Central Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed December 11, 1951 19
Application for plugging filed (orally) December 11, 1951 19
Application for plugging approved " December 11, 1951 19
Plugging commenced December 11, 1951 19
Plugging completed December 11, 1951 19
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|-----|-------|--------|------------|
| Surface | | 0 | 228 | 8 5/8 | 228 | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from total depth to 228 feet
Set plug at 228 feet and ran 15 sacks cement to 188 feet
Filled hole with heavy mud from 188 feet to 35 feet
Set plug at 35 feet and ran 10 sacks cement to cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Westgate-Greenland Oil Company
Address 1009 Central Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
G. E. Bitler (employee of owner) or (owner or operator)

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. E. Bitler
1009 Central Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of December, 1951
Esther Russell
Notary Public.

My commission expires May 25, 1953.

23-8390-s 6-51-20M

PLUGGING
FILED DEC 21 1951
300X

DEC 14 1951
12-14-51

DRILLER'S LOG

COMPANY: Westgate-Greenland Oil Company
 CONTRACTOR: Jackson Drilling Corporation
 FARM: Sutton No. 1
 LOCATION: NW NW SW Section 21-22-14W
 Stafford County, Kansas
 COMMENCED: November 29, 1951
 COMPLETED: December 11, 1951
 ELEVATION: 1954 DF

| | | | |
|------|----|------|---------------------|
| 0 | to | 100 | Sand |
| 100 | to | 228 | Shale and shells |
| 228 | to | 325 | Shale |
| 325 | to | 420 | Sand |
| 420 | to | 876 | Shale |
| 876 | to | 900 | Anhydrite |
| 900 | to | 1685 | Shale and shells |
| 1685 | to | 1985 | Lime and shale |
| 1985 | to | 2098 | Lime |
| 2098 | to | 2125 | Lime and shale |
| 2125 | to | 2350 | Lime |
| 2350 | to | 3505 | Lime - shale |
| 3505 | to | 3510 | Shale |
| 3510 | to | 3520 | Brown lime |
| 3520 | to | 3740 | Lansing lime |
| 3740 | to | 3788 | Lime -shale |
| 3788 | to | 3834 | Cherty Conglomerate |
| 3834 | to | 3859 | Conglomerate |
| 3859 | to | 3918 | Cherty lime |
| 3918 | to | 3964 | Cherty lime & shale |
| 3964 | to | 3979 | Shale and lime |
| 3979 | to | 4013 | Arbuckle |
| | | 4013 | T. D. (RB) |

Set 228 feet 8 5/8" Surface-24#. Cemented with 225 sacks cement and 3 sacks calcium chloride.

Drill Stem Test: 3637-48, open 50 minutes, weak blow 18 minutes, Recovered 30' mud, BHP 780#.

TOPS: Heebner 3380. Brown Lime 3508. Kansas City 3518.
 Base KC 3751. Conglomerate 3803. Viola 3842.
 Simpson 3906. Arbuckle 3976.

Dry, plugged and abandoned

DEC 14 1951

C E R T I F I C A T E

I, G. E. Bitler, do hereby certify that the above and foregoing is a true and correct copy of log of the Sutton #1, Section 21-22-14W, Stafford County, Kansas, as reflected by files of the Westgate-Greenland Oil Company.

G. E. Bitler
 G. E. Bitler

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 13th day of December, 1951.

Esther Russell
 Notary Public

My commission expires May 25, 1953.

RECORDED
 13
 1951