


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Stafford County. Sec. 21 Twp. 22S Rge. 14W ~~XXXX~~
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NE SW NW
Lease Owner Parrish Oil Company
Lease Name Neeland Well No. 1
Office Address 120 No. Market, Suite 201, Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole
Date Well completed December 18, 1976
Application for plugging filed Verbal Application 1976
Application for plugging approved Verbal Approval 1976
Plugging commenced December 18, 1976
Plugging completed December 18, 1976
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 3760'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	312'	None

RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1976

12-23-76

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Filled hole with heavy rotary mud from 3,760 ft. (rotary total depth)
to 300 ft. Set plug at 300 ft. and cemented with 35 sacks cement.
Filled hole with heavy rotary mud from 300 ft. to 40 ft.
Set solid plug at 40 ft. and cemented to cellar with 15
sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton
Oil Well cementing pump truck through 4-1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick
I, Dean Britting, Agent (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 No. Main, Wichita, Kansas 67202
(Address)

Subscribed and Sworn to before me this 22nd. day of December, 1976

My commission expires June 30, 1978

Elsie Willison Notary Public.

15-185-20701-0000

KANSAS GEOLOGICAL SOCIETY API NO. - 15-185-20,701
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Parrish Oil Company

SEC. 21 T. 22S R. 14W

FARM Mceland

NO. 1

LOC. NE SW NW

TOTAL DEPTH 3,760'

COMM. December 11, 1976

COMP. December 18, 1976


COUNTY Stafford

KANSAS

SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED December 22, 1976



CASING

20
15
12
13

10
8
6
5

-5/8" 312' cemented w/225 sxs cement ELEVATION 1925 KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Shale	314'
Shale	1,655'
Shale and Lime	1,745'
Shale with Lime Streaks	1,967'
Shale	2,085'
Lime and Shale	2,280'
Shale and Lime	2,500'
Lime and Shale	2,880'
Shale and Lime	3,325'
Lime and Shale	3,655'
Lime	3,760'
Rotary Total Depth	3,760'

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1976

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the above and foregoing
to be a true and correct log of the above
described well as shown by the drilling
reports.

H-30, INC.


Sean Britting
Sean Britting

State of Kansas

County of Sedgwick

ss:

Subscribed and Sworn to before me a Notary
Public in and for said county and state
this 22nd. day of December, 1976.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

June 30, 1978