

DRILLERS LOG

COMPANY: Westgate-Greenland Oil Co
 CONTRACTOR: Jackson Drilling Corporation
 FARM: Gore #1
 LOCATION: NE NE NW Section 15-22-14W
 Stafford County, Kansas
 COMMENCED: February 18, 1952
 COMPLETED: March 6, 1952
 ELEVATION: 1940 DF

0	to	140	Sand
140	to	155	Shale
155	to	170	Hard Sand W/pyrite
170	to	247	Shale and shells
247	to	270	Shale
270	to	365	Sand W/shale streaks
365	to	660	Red bed, sand & shale streaks
660	to	832	Red bed
832	to	856	Anhydrite
856	to	1315	Shale and shells
1315	to	1515	Shale and shells W/salt
1515	to	1605	Shale and lime
1605	to	1615	Shale
1615	to	1655	Shale and lime
1655	to	1710	Lime W/shale
1710	to	2055	Lime
2055	to	2085	Lime and shale
2085	to	2140	Lime
2140	to	3167	Lime and shale
3167	to	3214	Lime
3214	to	3245	Shale and silt
3245	to	3294	Lime and shale
3294	to	3346	Lime
3346	to	3412	Shale and lime
3412	to	3444	Shale
3444	to	3450	Brown lime
3450	to	3458	Shale and lime
3458	to	3675	Lime
3675	to	3695	Shale and lime
3695	to	3746	Lime and shale W/chert
3746	to	3783	Viola lime and chert
3783	to	3830	Shale and lime W/chert
3830	to	3848	Arbuckle lime
3848	to	3869	Arbuckle W/chert
3869	to	3880	Arbuckle
		3880	T. D. RB

Set 249 feet of 8 5/8" 24# surface pipe. Cemented with 200 sacks cement and 2 sacks calcium chloride.

Drill Stem Tests: 3479-3527, 1 hr, rec. 120' mud, 1150# BHP
 3564-3600, 3/4 hr, rec. 20' mud, 1020# BHP
 3604-42, 1 hr, 30' sl OCM, no BHP.

TOPS: Anhydrite 832. Kansas City 3452. Cherty Viola 3733
 Heebner 3315. Base K. C. 3674. Simpson 3779
 Brn. Ls 3441. Cherty Cong 3724. Arbuckle 3828

RUN SCHLUMBERGER

DRY, PLUGGED AND ABANDONED

PLUGGING
 FILE SEC 15 T 22R14W
 BOOK PAGE 111 LINE 4V

C E R T I F I C A T E

I, Don allen, do hereby certify that the above and foregoing is a true and correct copy of log of the Gore #1, NE NE NE Section 15-22-14W, Stafford County, Kansas, as reflected by files of the Jackson Drilling Corporation.

Don Allen
Don Allen

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 7th day of March, 1952.

Esther Unsell
Esther Unsell, Notary Public

My Commission expires May 25, 1953.