


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
300 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD



Stafford County. Sec. 15 Twp. 22S Rge. (E) 11 (W)  
Location as "NE/CNW/SWK" or footage from lines SW SE SE  
Lease Owner Petroleum, Inc.  
Lease Name SMITH 'T' Well No. 1  
Office Address 311 East Third, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 21 19 55  
Application for plugging filed August 21 19 55  
Application for plugging approved August 21 19 55  
Plugging commenced August 21 19 55  
Plugging completed August 21 19 55  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. W. H. Horner, Great Bend, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3690 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	206'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded up with heavy mud to 295' and set first wooden plug, placed 1/2 sack hulls on top of plug, displaced 20 sacks cement through drill pipe on top of hulls. Mudded up to 35' and set second plug with 1/2 sack hulls on top of plug, with 10 sacks cement to base of well cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 10 1955  
CONSERVATION DIVISION  
Wichita, Kansas

9-10-55

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Garvey Drilling Company  
Address R. R. #2 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Karl E. Becker (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Karl E. Becker  
311 East Third, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 22nd day of August, 19 55

My commission expires August 8, 1959

Gloria Morrison  
Notary Public.

GLORIA MORRISON  
NOTARY PUBLIC  
My commission expires August 8, 1959

PLUGGING  
FILE SEC 15 T 22 R 14 W  
BOOK PAGE 46 LINE 11

# WELL LOG

15.185.00799-0000

COMPANY **Petroleum, Inc.**

SEC. **15** T. **22S** R. **14W**

FARM **SMITH 'T'** NO. **1**

LOC. **SW SE SE**  
**280' FSL**  
**990' FEL**

TOTAL DEPTH **3690'**

COUNTY **Stafford**

COMM. **August 13, 1955** COMP. **August 21, 1955**

CONTRACTOR **Garvey Drilling Company**


CASING **8-5/8" @ 206' w/150 sax**

ELEVATION **1936' DF**  
**1938' RB**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

15	Sandy Clay
195	Sand
220	Yellow Clay
250	Blue Shale
375	Blue Shale & Sand
450	Sandy Red Rock
830	Red Bed & Sand
865	Anhydrite
1215	Shale
1770	Shale & Shells
1970	Lime & Shale
2135	Lime & Shale Streaks
2230	Lime
2275	Shale & Shells
3195	Shale & Lime
3340	Lime
3425	Lime & Shale
3690	Lime

### Sample Tops

Heebner:	3317	(-1379)
Toronto:	3334	(-1396)
Douglas:	3352	(-1414)
Brown Lime:	3443	(-1505)
Lansing:	3455	(-1517)

R.T.D. 3690'

**RECEIVED**  
STATE CORPORATION COMMISSION  
SEP 10 1955  
CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
FILE SEC 15 T 22 R 14 W  
BOOK PAGE 146 LINE 11

State of KANSAS }  
County of SEDGWICK } SS:

I, Karl E. Becker of Petroleum, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the SMITH 'T' #1 well

Subscribed and sworn to before me this 30th day of August 19 55

My Commission Expires: August 8, 1959

Karl E. Becker  
Glenn Morrison  
NOTARY PUBLIC