


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Pawnee County. Sec. 32 Twp. 22S Rge. 15W (E) (W)  
Location as "NE/CNW/SW" or footage from lines C N/2 N/2 NW  
Lease Owner Hellar Drilling Company, Inc.  
Lease Name "A" Barstow Well No. 2 "A"  
Office Address 1014 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 15, 19 61  
Application for plugging filed March 15, 19 61  
Application for plugging approved March 15, 19 61  
Plugging commenced March 15, 19 61  
Plugging completed March 15, 19 61  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, orally

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3983 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	225'	8 5/8"	250.59'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud to 220'. Set first plug at 220' w/20 sacks cement and 1/2 sack hulls. Filled hole with mud to 30'. Set second plug at 30' with 10 sacks cement and 1/2 sack hulls.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 28 1961  
3-28-61  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Hellar Drilling Company, Inc.  
Address 1014 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
D.L. Hellar, President, Hellar Drilling Co. (employer/owner) (owner ~~proprietor~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D.L. Hellar  
1014 Union Center  
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of March, 19 61  
Manda Lou Bruce  
Notary Public.

My commission expires March 6, 1965

WELL LOG

OWNER:  
LEASE:  
LOCATION:

Hellar Drilling Company, Inc.  
"A" Barstow #2 "A"  
C N/2 N/2 NW (22' South of  
"A" Barstow #2) Section 32-22S-15W  
Pawnee County, Kansas  
March 3, 1961  
March 15, 1961  
Set 8-5/8" surface casing  
@ 225' w/200 sacks cement.

COMMENCED:  
COMPLETED:  
CASING:

		Elevation	KB 2008
0 - 100	Sand, shells		
100 - 225	Shale, shells		
225 - 400	Blue shale, red bed		
400 - 488	Dakota sand	Anhydrite	940 /1068
488 - 939	Red bed	Heebner	3418 -1418
939 - 965	Anhydrite	Brown Lime	3534 -1526
965 - 1135	Shale, shells	Lansing-Kansas City	3546 /1538
1135 - 1825	Shale	Conglomerate	3878 -1870
1825 - 1915	Salt section	Viola	3890 -1882
1915 - 2075	Shale, lime	Simpson shale	3940 -1932
2075 - 2414	Lime, shale	Arbuckle	3979 -1971
2414 - 2955	Shale, lime		
2955 - 3075	Lime, shale		
3075 - 3144	Topeka lime		
3144 - 3195	Lime		
3195 - 3260	Lime, shale		
3260 - 3393	Lime		
3393 - 3503	Lime, shale		
3530 - 3585	Lime		
3585 - 3615	Lansing-Kansas City		
3615 - 3895	Lime		
3895 - 3943	Viola		
3943 - 3950	Cherty lime		
3950 - 3965	Simpson shale		
3965 - 3973	Simpson sand		
3973 - 3983	Arbuckle		
3983	Rotary Total Depth D & A		

RECEIVED  
STATE CORPORATIONS COMMISSION  
MAR 28 1961  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          ) SS:  
COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the "A" BARSTOW #2 "A", located in the C N/2 N/2 NW of Section 32-22S-15W, Pawnee County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

BY *D. L. Hellar*  
D. L. Hellar, President

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 23rd day of March, 1961.

*Wanda Lou Buech*  
Notary Public

My commission expires March 6, 1965.