

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-21746-00-00  
Spot: CSWSESW Sec/Twnshp/Rge: 28-23S-11W  
380 feet from S Section Line, 1650 feet from W Section Line  
Lease/Unit Name: RILEY Well Number: 24-28-1  
County: STAFFORD Total Vertical Depth: 3739 feet

Operator License No.: 100  
Op Name: KANSAS CORPORATION COMMISSION  
Address: 130 S MARKET RM 2078  
WICHITA, KS 67202

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 286 WITH 250 SX CMT  
Production: Size 4.5 feet: 3737 WITH 225 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/30/2001 4:30 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Revd. from: RICHARD LACEY Company: KCC Phone: (620) 225-8888

Proposed Plugging Method: SAND BOTTOM TO 3290' & PLACE 4 SX CMT ON TOP OF SAND. FREEPOINT AND RECOVER CASING PULLING TO 600'. SPOT 10 SX GEL & 50 SX CMT AT 600'. PULL CASING TO 310' & SPOT 50 SX CMT. PULL CASING TO 40' & CIRCULATE CMT TO SURFACE WITH 10 SX CMT

Plugging Proposal Received By: RICHARD LACEY

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/30/2001 5:30 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 3440-3448'. SANDED BACK TO 3250' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2213' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

*Stephen J. Pfeifer*  
(TECHNICIAN)

RECEIVED

NOV 09 2001

KCC WICHITA

11-9-01

NOV 07 2001

*AP*

Form SP-23