

120822

9-2

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,891-0000
NE SE SE, SEC. 18, T 22 S, R 12 W/E
990 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7383
Operator: Grady Bolding Corporation
Name & Address P.O. Box 486
Ellinwood, KS 67526

Lease Name Teichmann Well # 1
County Stafford
Well Total Depth 3810 123.82 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 255

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kincaid Well Service, Inc. License Number 7252

Address P.O. Box 276, Ellinwood, KS 67526

Company to plug at: Hour: 2:30 p.m. Day: 2 Month: 9 Year: 19 93

Plugging proposal received from Grady Bolding

(company name) Grady Bolding Corp. (phone) 316-564-2240

were: 5 1/2" at 3807' w/140 sx cement, Perfs at 3658-62, 3672-83'

1st plug sand 5 1/2" casing back to 3600' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper
plug and pump 100, sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:45 p.m. Day: 2 Month: 9 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3400' and dumped 5 sx cement on
top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Pumping pressure 0-600 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1859' of 5 1/2" casing.
(Additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
SEP 09 1993
9-93
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE SEP 14 1993 observe this plugging.

INV. NO. 38627

Signed Duane Rankin
(TECHNICIAN)