

1 120475

10-1

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,720-0000

N/2 SE, SEC. 18, T 22 S, R 12 W/E

2310 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30326

Lease Name Teichmann Well # 1

Operator: Williford Oil

County Stafford 123.50

Name & Address RR 1 Box 35

Well Total Depth 3800 feet

Alden, KS 67512

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 268

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling License Number 5929

Address 310 W. Central, #117, Wichita, KS 67202

Company to plug at: Hour: 10 a.m. Day: 1 Month: 10 Year: 19 90

Plugging proposal received from John Armbruster

(company name) Duke Drilling (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 690-715'

1st plug at Arbuckle with 40 sx cement, 2nd plug at 715' with 50 sx cement,

3rd plug at 300' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:15 p.m. Day: 1 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 3730' with 40 sx cement,

2nd plug at 710' with 50 sx cement,

3rd plug at 300' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (I could not observe this plugging.)

DATE 10-19-90

INV. NO. 29677

Signed [Signature] (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION

10-9-90 CONSERVATION DIVISION Wichita, Kansas

