

1 080542

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,467-0000

N/2 N/2 NE SEC. 18, T 22 S, R 12 W/E

4950 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4655

Lease Name Harms "A" Well # 7

Operator: BHP Petroleum (Americas), Inc.

County Stafford 119.89

Name & Address 925 Patton Road

Well Total Depth 3689 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 7/8" feet 697

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, Kansas 67524

Company to plug at: Hour: 10:00 am Day: 7 Month: August Year: 1986

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling (phone) (316) 938-2457

were: 5 1/2" at 3688' Perfs Open hole 3688-89'

1st plug sand back to 3638' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, and 120 sx cement with 2 sx hulls mixed in.

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:45 am Day: 7 Month: August Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded bottom back to 3638' and dumped 5 sx cement

on top of sand through a bailer, 2nd plug squeezed the well with 3 sx hulls, and

120 sx cement with 2 sx hulls mixed in.

Maximum pressure 800 psi and shut in 450 psi.

Remarks: Used ALC cement pumped by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

AUG 12 1986

DATE _____

INV. NO. 14704

8-7

8-12-86

8-12-1986

Signed _____

J. H. Metz
(TECHNICIAN)



GAMMA-GUARD SIDEWALL NEUTRON LOG

COMPANY ENERGY RESERVES GROUP, INCORPORATED WELL HARMS #7 FIELD DRACH County STAFFORD State KANSAS	COMPANY ENERGY RESERVES GROUP, INCORPORATED WELL HARMS #7 FIELD DRACH COUNTY STAFFORD STATE KANSAS Location N/2 - N/2 - NE Other Services: BOTTOM GAMMA Sec. 18 Twp. 22S Rge. 12W		
Permanent Datum GROUND LEVEL Elev. 1873' Log Measured From KELLY BUSHING, 5 Ft. Above Perm. Datum Drilling Measured From KELLY BUSHING, 5' ABOVE G.I.			
Elev.: K.B. 1878' D.F. _____ G.L. 1873'			
Date	12-8-81	12-8-81	12-8-81
Run No. ONE	GAMMA	NEUTRON	GUARD
Depth—Driller	3689'	3689'	3689'
Depth—Welex	3695'	3695'	3695'
Btm. Log Inter.	3694'	3694'	3681'
Top Log Inter.	0'	2500'	698'
Casing—Driller	8-5/8" @ 697'	@	@
Casing—Welex	8-5/8" @ 698'		
Bit Size	7-7/8"		
Type Fluid in Hole	STARCH MUD		
Dens. Visc.	9.9 57		
pH Fluid Loss	6.3 9.8ml	ml	ml
Source of Sample	FLOW LINE		
R _m @ Meas. Temp.	.21 @ 55°F	@	@ °F
R _m @ Meas. Temp.	.142 @ 57°F	@	@ °F
R _{mc} @ Meas. Temp.	.6 @ 58°F	@	@ °F
Source R _m R _{mc}	MEASURED		
R _m @ BHT	.11 @ 109°F	@ °F	@ °F
Time Since Circ.	10 HOURS		
Max. Rec. Temp.	109°F @ T.D.	°F @	°F @
Equip. Location	3398 GREAT BEND		
Recorded By	M. SCHIRADER		
Witnessed By	MR. SHAFFER		

RECEIVED
 STATE REGISTRATION COMMISSION
 SONS. DIV. WIC @ RS
JUL 27 1985

Fold Here