

1052414
TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-21,468-0000
NE NW NW SEC. 18, T 22 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 4950 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4620 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HARMS WELL # 8

TECHNICIAN'S PLUGGING REPORT 8/7

COUNTY STAFFORD

119.60

OPERATOR LICENSE # 6170

WELL TOTAL DEPTH 3680 FEET

OPERATOR: GLOBE OPERATING, INC. PRODUCTION CSG: SIZE 5 1/2" @ 3680' WITH 200 SX

NAME AND PO BOX 12 SURFACE CASING: SIZE 8 5/8" @ 713' WITH 490 SX

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR DS&W WELL SERVICING LICENSE NUMBER 6901

ADDRESS PO BOX 231 CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 2:00 AM DAY: 07 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM BRIAN FRENZEL

(COMPANY NAME) DS&W (PHONE) 316-587-3361

WERE: PERFS AT 3400-64 & 3348-57

SAND TO 3400' AND 5 SX CEMENT. PUMP DOWN 8 5/8" 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 100 SX CEMENT. TOOK 1600 PSI TO START PUMPING. MAXIMUM PRESSURE 550 PSIG. SHUT IN PRESSURE 400 PSIG.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 4:19 PM DAY: 07 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT _____

SAND TO 3400' AND 5 SX CEMENT. PUMP DOWN 8 5/8" 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 100 SX CEMENT. TOOK 1600 PSI TO START PUMPING. MAXIMUM PRESSURE 550 PSIG. SHUT IN PRESSURE 400 PSIG.

RECEIVED
STATE CORPORATION COMMISSION

8-15-00
AUG 15 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1800' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM. CONSERVATION DIVISION
Wichita, Kan. 67202

I (DID) OBSERVE THIS PLUGGING.

INVOICED
DATE 8/21/00
INV. NO. 1060443

SIGNED

Richard M. Lacey
(TECHNICIAN)

FORM CP-2/3