

1060849

210-R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,081-0000

NE NW NW, SEC. 32, T 22 S, R 11 (W) ~~XX~~

4950 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6588

Lease Name Heyen Well # 1

Operator: Woodman-Iannitti Oil Co.

County Stafford 116.03

Name & Address P. O. Box 308

Well Total Depth 3570 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 291

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address P. O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 3:00 pm Day: 21 Month: April Year: 19 86

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 5 1/2" at 3568' PBTD 3542' Perfs at 3530-34'

1st plug sand back to 3475' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 pm Day: 21 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3475' and dumped 5 sx cement on top of

sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement,

10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 700 psi and shut in 350 psi

Remarks: Recovered 2800' 5 1/2" casing. Used 60/40 Pozmix 6% gel by BJ-Titan.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

APR 29 1986

DATE _____

INV. NO. 13609

4-2/MAY 28 1986

Signed Paul A. Luthi
(TECHNICIAN)

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
4-26-86
APR 28 1986