

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185-21780-0000

SE NE SW, Sec. 28, T 22 S, R 11 W/E

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7383

Lease Name Lofland Well # 1

Operator: Grady Bolding Corp.  
Name & Box 244  
Address Great Bend, KS 67530

County Stafford

Well Total Depth 3690 feet 119.92  
Production

~~XXXXXXXX~~ Conductor Pipe: Size 5 1/2 feet 3689

Surface Casing: Size 8 5/8 feet 288

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 2:00 pm Day: 12 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO D. B. Pulley

(company name) Rockhold Engineering (phone) 316-792-2506

were: 1st plug sand bottom back to 3065' and dump 5 sx cement on sand through  
bailer. 2nd plug through head in sequence 3 sx hulls, 10 sx gel, 50 sx cement and  
10 sx gel and 1 sx hulls and released 8 5/8 rubber plug and pumped another 125 sx  
cement.

Signed Steve Chumant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 4:40 pm Day: 12 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 1st plug sand bottom back to 3065' and dump 5 sx cement on  
sand through bailer. 2nd plug through head in sequence - 3 sx hulls, 10 sx gel, 50  
sx cement and 10 sx gel, and 1 sx hulls and released 8 5/8 rubber plug and pumped  
another 125 sx cement.

Remarks: They recovered 2900' of 5 1/2" production casing. Sun Cementing  
accomplished plugging with 50/50 Poz with 2% gel, 3% cc. Maximum pressure 600#  
and shut in pressure at 300#.

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / did not) observe this plugging.

Signed Steve Chumant  
(TECHNICIAN)

INVOICED

RECEIVED  
STATE CORPORATION COMMISSION

DATE 1-26-84 JAN 23 1984 1-23-84

INV. NO. 9256-W CONSERVATION DIVISION  
Wichita, Kansas