

To: 120749 11-6
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,772-0000 27R
NW NW NW, SEC. 19, T 22 S, R 12 W/E
4950 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5614
Operator: Hutchinson Oil Company
Name & Address 105 S. Broadway, Ste. 470
Wichita, KS 67202

Lease Name Alpers Well # 2-19
County Stafford 123.50
Well Total Depth 3800 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111
Address P.O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 1 p.m. Day: 6 Month: 11 Year: 19 92
Plugging proposal received from James Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 3797' w/140 sx cement, PBD 3670', Perfs at 3376-3772'
1st plug sand back to 3325' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper
plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 2 p.m. Day: 6 Month: 11 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3325' and dumped 5 sx cement on
top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10
sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.
Pumping pressure 0-300 psi and shut in 100 psi.

11-12-92 NOV 12 1992

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (I did not) observe this plugging.

DATE 11-24-92
INV. NO. 36915

Signed Steve Middleton
(TECHNICIAN)