

To: 1 031179
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-25
API NUMBER 15- 185-22,788-0000 2-45
NW NW SW, SEC. 19, T 22 S, R 12 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039
Operator: L.D. Drilling, Inc.
Name & Address: RR 1, Box 183 B
Great Bend, KS 67530

2310 feet from S section line
4950 feet from E section line
Lease Name Curtis Well # 1
County Stafford 122.16
Well Total Depth 3759 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 332

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 10 a.m. Day: 25 Month: 10 Year: 1991

Plugging proposal received from Bessie
(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: 4 1/2" at 3756' w/150 sx cement, PBT'D 3600', Perfs at 3723-29, 3550-55'
1st plug sand back to 3500' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 120 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:10 p.m. Day: 25 Month: 10 Year: 1991

ACTUAL PLUGGING REPORT 1st plug sanded back to 3500' and dumped 4 sx cement on top of
sand through bailer,
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released
8 5/8" wiper plug and pumped 120 sx cement.
Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1798' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICE

DATE 11-13-91
INV. NO. 33702

RECEIVED
OBSERVE THIS PLUGGING
STATE CORPORATION COMMISSION

Signed Steve Durrant
(TECHNICIAN)

OCT 29 1991

10-29-91