

1 040031

12-23-87 15-185-30262-0000

API NUMBER 15- Drill Completion Date 4/21/66

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SE NE, SEC. 17, T. 22 S, R. 12 W/EX
3630 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5339
Operator: Bergman Oil Company
Name & Address: 520 Union Center
Wichita, KS 67202

Lease Name Milam Well # 1
County Stafford 120.51
Well Total Depth 3708 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 225

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Bergman Oil Company License Number 5339
Address 520 Union Center, Wichita, KS 67202

Company to plug at: Hour: 2 p.m. Day: 23 Month: 12 Year: 19 87

Plugging proposal received from Lloyd Davis

(company name) Bergman Oil Company (phone) 316-267-5291

were: 4 1/2" at 3695' PBSD 3480' Perfs at 3460-62'

1st plug fill 4 1/2" with 3 sx hulls and Econolite cement to top,
2nd plug pump 100 sx Econolite down 8 5/8" annulus.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:45 p.m. Day: 23 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 300 lbs. hulls in w/first
of cement and 110 sx cement. Pumping pressure 50-200 psi and shut in 100 psi.

2nd plug pumped down annulus with 75 sx cement. Pumping pressure 100-300 psi and shut in
200 psi.

Remarks: Used ATL cement by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED (and/or observe this plugging.)

Signed Stephen J. Pfeifer
(TECHNICIAN)

DATE 11-88

INV. NO. 19355
12-23

FEB 24 1988