

1 050181

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,965-0000

NE SW SE, SEC. 22, T 22 S, R 12 W/E

990 feet from N/S section line

1650 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8625

Lease Name Alpers Well #3

Operator: VAC Petroleum Company

County Stafford

Name & Address 6225 East Kellogg

Well Total Depth 3740 121.55 feet

Wichita, KS 67218

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 290

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Wheatstate Drilling License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 10:00 am Day: 28 Month: March Year: 19 84

Plugging proposal received from Steve Fellers

(company name) Wheatstates (phone) 316-672-7514

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3660' with 50 sx cement

2nd plug at 630' with 50 sx cement

3rd plug at 330' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement. Plug water well with 5 sx cement

Plugging Proposal Received by Richard W. Lucas (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:30 pm Day: 28 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 3660' with 50 sx cement, 2nd plug at 630' with

50 sx cement, 3rd plug at 330' with 40 sx cement, 4th & 5th plugs - solid bridge -

hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate

rathole with 15 sx cement. Plug water well with 5 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-3-84

RECEIVED STATE CORPORATION COMMISSION

APR 03 1984

Signed Richard W. Lucas (TECHNICIAN)

INV. NO. 1019 3-28 APR 25 1984 CONSERVATION DIVISION Wichita, Kansas

FORM CP-2/3 Rev. 01-84