

1051700

7-29

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 13-185-22,200-0000
SE NE SW, SEC. 22, T. 22 S, R. 12 W XX
1650 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039
Operator: L.D. Drilling, Inc.
Name & Address: RR 1, Box 183B
Great Bend, KS 67530

Lease Name Alpers Ukens Well # 3
County Stafford
Well Total Depth 3740 121.55 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 307

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 29 Month: 7 Year: 1993

Plugging proposal received from Darrell Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 3737' w/250 sx cement, PBTD 3715'. Perfs at 3385-?
1st plug sand back to 3330' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 12:20 p.m. Day: 29 Month: 7 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 3330' and dumped 5 sx cement on top of sand
through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released
8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 100 psi.

RECEIVED
STATE CORPORATION COMMISSION

8-3-93

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2391.75' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE: 8-6-93

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 38261