

1051701

7-29

API NUMBER 15-185-22,014-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE SE SW, SEC. 22, T. 22 S, R. 12 W&E

990 feet from S section line

2228 feet from W E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lease Name Ukens Well # 1

Operator: L.D. Drilling, Inc.

County Stafford

Name & Address

RR 1, Box 183B

Well Total Depth 3760 122,20 feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 29 Month: 7 Year: 19 93

Plugging proposal received from Darrell Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 3759' w/150 sx cement, PBD 3705', Perfs at 3708-11, 3695-98'

1st plug sand back to 3650' and dump 5 sx cement on top of sand through bailer.

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:20 a.m. Day: 29 Month: 7 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3650' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released

8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 600 psi and shut in 300 psi.

RECEIVED STATE CORPORATION COMMISSION

AUG 3 1993 8-3-93

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2354.5' of 5 1/2" casing.

INVOICED

I (did / ~~XXXXXX~~) observe this plugging.

DATE 8-6-93

Signed Richard M Lacey (TECHNICIAN)

INV. NO. 38259