

1 120427

6-7

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,243-0000

S/2 SW SE, SEC. 22, T 22 S, R 12 W/E

330 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4399

Lease Name Alpers Well # 1

Operator: VAC Petroleum Co., Inc.

County Stafford 119.83

Name & Address Box 780106

Well Total Depth 3687 feet

Wichita, KS 67278-0106

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 296

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pulling, Inc. License Number 4635

Address Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 7 Month: 6 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pulling, Inc. (phone) 316-793-9711

were: 5 1/2" at 3679' Open hole

1st plug sand back to 3630' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and

100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 7 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3630' and dumped 5 sx cement

on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls and 100 sx cement.

Pumping pressure 0-750 psi and shut in 250 psi.

Plate and 2" collar welded on 8 5/8".

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2047' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (copy to customer) observe this plugging.

DATE 6-25-90 JUN 13 1990

Signed Duane Rankin (TECHNICIAN)

INV. NO. 28471

6-13-90