

To: 1 052091 12-5
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 185-22,051-0000
SW SW SE, SEC. 22, T 22 S, R 12 W/X
330 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6039
Operator: L.D. Drilling, Inc.
Name & Address
Rt. 1, Box 183-B
Great Bend, KS 67530

Lease Name Alpers B Well # 4
County Stafford 120.25
Well Total Depth 3700 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 12 p.m. Day: 5 Month: 12 Year: 19 96

Plugging proposal received from Kent Strube
(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

Work: 5 1/2" at 3684' w/150 sx cement, Perfs at 3342-3497'

1st plug sand back to 3290' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Bill Johnson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 5 Month: 12 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3320' and dumped 5 sx cement on top of sand
through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, released 8 5/8" wiper plug and pumped 125 sx cement. 12-9-96

Maximum pressure 600 psi and shut in 300 psi;

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1783' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Richard W. Lacy (TECHNICIAN)

DATE DEC 12 1996
INV. NO. 47166