

To: 1090652
STATE CORPORATION COMMISSION

API NUMBER 15- 185-22,114-0000

Wichita State Office Bldg. PLUGGING SECTION W/2. W/2. SE, SEC. 22, T 22 S, R 12 W/2
130 S. Market, Room 2078
Wichita, KS 67202

1320 feet from S section line
2310 feet from E section line
Lease Name Alpers Well # 5

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039 *a-21*

Operator: L.D. Drilling, Inc.
Name & Address: RR 1, Box 183 B
Great Bend, KS 67530

County Stafford
Well Total Depth 3770 *122.53* feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 294

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 1:15 p.m. Day: 21 Month: 2 Year: 1996

Plugging proposal received from L.D. Davis

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

Notes: 4 1/2" at 3769' w/175 sx cement, PBTD 3769', Perfs at 3698-3702, 3469-86, 3487-96, 3494-3513'

1st plug sand back to 3400' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

2-26-96
RECEIVED
TRANS
CORP
COMM
6%
1996 FEB 26

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 21 Month: 2 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 3400' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 750 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2219' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby do not observe this plugging.

DATE 3-4-96
INV. NO. 44921

Signed [Signature]
(TECHNICIAN)