

1052227

TO:

2-16

API NUMBER 15-185-21,637-0000

STATE CORPORATION COMMISSION

NE NE NE, SEC. 22, T 22S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION

4950 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME Durham WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY Stafford 122.53

OPERATOR LICENSE # 6039

WELL TOTAL DEPTH 3770 FEET

OPERATOR: L.D. Drilling, Inc.

PRODUCTION CSG: SIZE 5 1/2" FEET 3768 w/175 sx

NAME AND RR 1, Box 183 B

SURFACE CASING: SIZE 8 5/8" FEET 298

ADDRESS Great Bend, KS 67530

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D/A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR D S & W Well Servicing, Inc. LICENSE NUMBER 6901

ADDRESS P.O. Box 231, Claflin, KS 67525-0231

COMPANY TO PLUG AT: HOUR: 9 a.m. DAY: 16 MONTH: 2 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM Kent Strube

(COMPANY NAME) D S & W Well Servicing, Inc. (PHONE) 316-587-3361

WERE: Perfs at 3692.5-3694.5'

1st plug sand back to 3640' and dump 5 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, release 8 5/8" wiper plug and pump 125 sx cement,

PLUGGING PROPOSAL RECEIVED BY Richard Lacey

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 11 a.m. DAY: 16 MONTH: 2 YEAR: 1998

ACTUAL PLUGGING REPORT TO 1st plug sanded back to 3640' and dumped 5 sx cement on top of

sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 500 psig and shut in 400 psig.

2-23-98

FEB 23 1998

REMARKS: Used 60/40 Pozmix 6% gel by Allied. Recovered 2720' of 5 1/2" casing.

IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey  
(TECHNICIAN) FORM CP-2/3

INVOICED

DATE FEB 25 1998

INV. NO. 50133

2-16