

1051315

6-8

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,512-0000

NW SW SE, SEC. 22, T 22 S, R 12 W/E

990 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4933

Lease Name Alpers Well # 2

Operator: VAC Petroleum Company, Inc.

County Stafford 120.32

Name & Address P.O. Box 780106

Well Total Depth 3702 feet

Wichita, KS 67278-0106

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 8 Month: 6 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 16-793-9711

were: 5 1/2" at 3702' Open hole at 3702'

1st plug sand back to 3650' and dump 5 sx cement on top of sand through bailer,

Spot plugs through tubing:

2nd plug at 900' with 50 sx cement and 10 sx gel,

3rd plug pump 100 sx cement at 320'.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 8 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3650' and dumped 5 sx cement on top of sand through bailer,

Spotted plugs through tubing after bullhead squeeze failed:

2nd plug pumped 50 sx cement and 10 sx gel at 900',

3rd plug pumped 100 sx cement at 320-0'.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2202' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOLVED
I did ~~not~~ observe this plugging.

DATE 6-25-90

6-12-90 Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 28472