

1 050773

API NUMBER 15- 083-21,241-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NW, SEC. 34, T 22 S, R 25 W

4620 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4808

Lease Name Shriwise Well # 21-34

Operator: Smokey Oil Company

County Hodgeman 15/78

Name & Address P. O. Box 2360

Well Total Depth 4670 Mississippi feet

Casper, WY 82602

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 634

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor True Drilling Company License Number 4708

Address P. O. Drawer 2360, Casper, WY 82602

Company to plug at: Hour: 12:00 pm Day: 24 Month: February Year: 19 86

Plugging proposal received from Buzz Montgomery

(company name) True Drilling (phone) 307-237-9301

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2466 Anhydrite 1725'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 30' below the base of the surface pipe with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 2:30 pm Day: 24 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1740' with 50 sx cement, 2nd plug at 660' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

MAR 4 1986

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE MAR 04 1986

Signed Richard W. Lacy (TECHNICIAN)

INV. NO. 12856

2-24

(see rules on reverse side)

Starting Date February 1986 month day year

API Number 15-083-21,241-0000

OPERATOR: License # 4808 Name Smokey Oil Company Address P. O. Box 2360 City/State/Zip Casper, WY 82602 Contact Person C. F. Pickard Phone (307)-266-0230

NE NW Sec 34 Twp. 22 S, Rg. 25M... 4620 Ft. from South Line of Section 3300 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 4708 Name True Drilling Company City/State Casper, WY 82602

Nearest lease or unit boundary line 660 feet County Hodgeman

Lease Name Shriwise Well # 21-34 Ground surface elevation 2466 feet MSL

Well Drilled For: Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

Depth to bottom of fresh water 200 Depth to bottom of usable water 600

Surface pipe by Alternate: 1 X 2 Surface pipe planned to be set 8-5/8" 24#, 600'

Conductor pipe required Projected Total Depth 4800 feet

Formation Mississippian

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date Jan 30 1986 Signature of Operator or Agent C. F. Pickard Title Engineer

For KCC Use: Conductor Pipe Required 600 feet per Alt. 1 This Authorization Expires 8-1-86 Approved By 2-4-86

Spud 12-13-86 Set 600'

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ .50 sx Base of Anhydrite feet depth with 10 sx of 2nd plug @ 50 sx 30' below base surf depth with 10 sx of 3rd plug @ 10 sx 40' below surf feet depth with 10 sx of 4th plug @ 15 sx in rat hole feet depth with 10 sx of 5th plug @ feet depth with 10 sx of (2) Rathole with sx (b) Mousehole with 10 sx

PUSHER A.E. Bump - Montgomery - TD 4670 FORMATION MISS SURFACE PIPE 634 @ 8 5/8 ANHYDRITE 1725 ELEVATION 2466 STARTING TIME & DATE 2-24 COMPLETION TIME & DATE 2:30pm 1st PLUG @ 1740 FT. W/ 50 SX 2nd PLUG @ 660 FT. W/ 50 SX 3rd PLUG @ 40 FT. W/ 10 SX 4th PLUG @ FT. W/ SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ 60/40 67% CEMENT COMPANY Hall Saw TECHNICIAN Kacey Platt

RECEIVED STATE CORPORATION COMMISSION

MAR 4 1986

CONSERVATION DIVISION Wichita, Kansas